

INSTALLATION AND TESTING OF A  
FLOW/LEVEL CONTROL SYSTEM

by

Tsiartas Lukas

Project Report

Submitted to

the Department of Mechanical Engineering  
of the Higher Technical Institute

Nicosia Cyprus

in partial fulfillment of the requirements

for the diploma of


TECHNICIAN ENGINEER

in

MECHANICAL ENGINEERING

June 1993

project M/661



### ACKNOWLEDGEMENTS

I wish to express my thanks to my project supervisor Mr. P. Eleftheriou for his usefull guidance during the process of completion of this project.

Also thanks are to Mr C. Kaloyirou Laboratory Assistant of the H.T.I. Plant laboratory.

Finally I would like to express my thanks to Miss Yioula Kalorkoti for typewriting this project and to everyone else who helped in the completion of this project.

## ABSTRACT

This project deals with the installation and testing of an automatic Flow/level Control system which will be used for experimental purposes at the H.T.I. Control Lab.

The system was installed on a trolley which was constructed to meet the needs of the system.

Most equipment used in the system were already on hand from a similar project performed by Hadjiloizis Kyriacos in 1986.

## CONTENTS

	<u>Page</u>
Acknowledgements	I
Abstract	II
Introduction	III
<b>Chapter 1: DESIGN ANALYSIS</b>	
1.1.	Problem definition 1
1.2.	Features 1
1.2.1.	Possible sensing methods 1
	1. Pressure sensing method 1
	2. Buddler or purge method 1
	3. Force transducer 2
	4. Motion transducer 2
	5. Sonic sensing emthod 3
	6. Radioisotopes sensing method 3
	7. Conductivity sensing method 4
	8. Capacitance sensing method 4
	9. Optical sensing method 5
	10. Hot wive sensing method 5
1.2.2.	Controllers 6
1.2.3.	Transmitters 8
1.2.4.	Control valves 9
1.2.5.	Piping arrangements 10
1.3.	Morphological analysis table 10
1.4.	Final solution 13
<b>Chapter 2: THEORETICAL ANALYSIS</b>	
2.1.	Derivation of the block diagram of the level control system 14
2.1.1.	Conditions of validity 15
2.1.2.	Tank dynamics 15
2.1.3.	Differential pressure transmitter's block diagram 17

2.1.4.	Controller's block diagram (PI)	18
2.1.5.	Complete block diagram of the level control system	19
2.2.	Derivation of the transfer function of the level control system	19
Chapter 3: INSTALLATION OF THE FLOW/LEVEL CONTROL SYSTEM		23
Chapter 4: TESTING CALIBRATION AND COMMISSIONING OF THE SYSTEM		24
4.1.	Sequential testing and commissioning	24
4.1.1.	Testing the accuracy of the pressure gauges	24
4.1.2.	Testing the control valve	24
4.1.3.	Calibration and commissioning the Transmitter	25
4.1.4.	Commissioning the Controller	26
4.2.	Loop commissioning	26
Chapter 5: PROCESS OPTIMIZATION		27
5.1.	Optimum settings of the Controller	27
5.2.	Optimum settings according to Ziegler and Nichols	27
Chapter 6: SUGGESTED EXPERIMENTS		30
	EXPERIMENT 1	30
	EXPERIMENT 2	33
	EXPERIMENT 3	34
COMMENTS		35

APPENDICES:	Appendix 1 - Transmitter	36
	Appendix 2 - Controller	37
	Appendix 3 - Control valve	38
	Appendix 4 - Instrument Specifications	39
	Appendix 5 - Detail Drawing of the control system	
REFERENCES		40